CRAVEN COUNTY

CRAVEN COUNTY SUBDIVISION ORDINANCE DRAFT

1984

The preparation of this Draft Subdivision Ordinance was financed in part through a grant provided by the North Carolina Coastal Management Program, through funds provided by the Coastal Zone Management Act of 1972, as amended, which is administered by the Office of Coastal Zone Management, National Oceanic and Atmospheric Administration.

2	CRAVEN COUNTY SUBDIVISION ORDINANCE
3	ARTICLE I
4	BASIS, 1994
5	1. Authority and Purpose
6 7 8	This Ordinance is entitled <u>Subdivision</u> <u>Ordinance for the County of Craven</u> and may be cited as the Subdivision <u>Ordinance</u> .
9 10 11 12 13 14 15 16 17 18 19 20 21 22 23	This Ordinance is adopted pursuant to Chapter 153A, Article 18, of the General Statutes of North Carolina for the purpose of supporting and guiding the proper subdivision and resubdivision of land within the subdivision jurisdiction of Craven County in order to promote the public health, safety and general welfare of its citizens and to promote the orderly growth of the County. Chapter 153A, Section 335 defines "subdivision" as "all divisions of a tract or parcel of land into two or more lots, buildings sites, or other divisions for the purpose of sale or building development (whether immediate or future) and includes all division of land involving the dedication of a new street or a change in existing streets; however, the following is not included within this definition and is not subject to any regulations enacted pursuant to this Part:
24 25 26 27 28	(1) The combination or recombination of portions of previously platted lots if the total number of lots is not increased and the resultant lots are equal to or exceed the standards of the county as shown in its subdivision regulations;
29 30 31	(2) The division of land into parcels greater than 10 acres if no street right-of-way dedication is involved;
32 33	(3) The public acquisition by purchase of strips of land for widening or opening streets; and
34 35 36 37 38 39	(4) The division of a tract in single ownership the entire area of which is no greater than two acres into not more than three lots, if no street right-of-way dedication is involved and if the resultant lots are equal to or exceed the standards of the county as shown by its subdivision regulations.

DRAFT

1

40 2. Jurisdiction

This Ordinance shall govern each and every subdivision of land within Craven County except that land within the subdivision jurisdiction of any municipality, unless such municipality shall have by resolution formally requested the County to enforce this Ordinance within the municipality's jurisdiction.

47 ARTICLE II

48 COMPLIANCE

49 l. Approval of Plat

No subdivision plat of land within the subdivision 50 jurisdiction of Craven County shall be filed or recorded by 51 the Register of Deeds for Craven County until it shall have 52 been submitted and approved in accordance with this Ordinance 53 and until such approval is entered on the face of the final 54 55 plat by the Chairman of, or other member authorized by, the Craven County Subdivision Review Board, hereinafter known as 56 the "Board". 57

58 2. Permits

59

61

62 63

65

66

60

No building permits shall be issued for, nor shall water, sewer, or other County facilities or services be extended to or connected with, any subdivision for which a plat is required to be approved until the General Development Plan has been approved by the Board.

64 ARTICLE III

GENERAL REQUIREMENTS FOR SUBDIVISIONS

1. Suitability of Land

67 Where land to be subdivided is found by the Board to be 68 subject to the conditions of flooding, improper drainage, severe erosion, slides, or to have other characteristics 69 which pose an ascertainable danger to health, safety, or 70 property, the subdivider shall take measures necessary to correct said conditions and to eliminate said dangers. In 71 72 73 making such determinations the Board shall take into 74 consideration official U. S. Department of Housing and Urban Development Flood Hazard Boundary Maps, the Craven County 75 Soil Survey, and recommendations of the Corps of Engineers, the Soil Conservation Service, U.S.D.A., and the Craven 76 77 County Board of Health. Any findings made by the Board pursuant to this section and the basis for said findings 78 79 08 shall be in writing and recorded in the minutes of the Board.

When the land to be subdivided falls within an area of Environmental Concern, the following shall be shown on such map: When this plat was prepared, the areas shown as areas of Environmental Concern on the plat met the standards of the North Carolina Coastal Resources Commission for such areas. A Coastal Area Management Act permit may be required for any development within those areas.

88 2. Streets

89 The General Development Plan must be accompanied by evidence satisfactory to the Board as to the proposed method 90 of street access, as prescribed herein, to all lots to be 91 92 platted, which evidence shall provide detailed information as 93 to proposed elevations, cut and fill, drainage, traffic 94 circulation and other construction details required by a municipality, the North Carolina Secondary Roads Council 95 96 and/or the North Carolina Department of Transportation (both of which are hereinafter referred to as "D.O.T."), or by the 97 98 The installation of all streets, in accordance with requirements set forth below, shall be required prior to 99 final plat approval unless otherwise permitted pursuant to 100 Further, 101 the subdivider shall meet Article V. requirements of North Carolina General Statute Section 136-102 103 102.6.

104 2.01 Municipal Streets

All streets to be built in an incorporated municipality having adopted this Ordinance shall be constructed as described on the approved General Development Plan and shall meet the minimum road construction standards of the municipality so that said streets, when completed, are eligible for maintenance by said municipality.

111 2.02 Public Streets

Unless otherwise designated by the Board pursuant to Section 2.03 of this Article, all streets to be built outside an incorporated municipality shall be designed, built, and dedicated in accordance with existing applicable policies and standards of D.O.T. so that said streets, when completed, are eligible for acceptance on the State Highway System.

118 2.03 Private Streets

119 Upon request the Board may permit certain streets to be 120 designated as private for the purposes of providing street 121 access to the following:

122 (a) Residential subdivisions with streets designed 123 to provide exclusive access only to said subdivision; or

	·
124 125 126	(b) Minor subdivisions with a street serving too few lots for inclusion into the North Carolina Secondary Road System.
127	Private streets may be established as follows:
128	2.031 Private Residential Streets
129 130 131 132 133 134 135 136 137 138 139	If an owners' association is established for perpetual ownership and maintenance of streets and rights-of-way within, and/or which provide exclusive access to a subdivision, then said streets and rights-of-way may be designated as "private residential streets". In such case the subdivider shall dedicate at least a 50 foot right-of-way to said owner's association but shall not be required to dedicate street right-of-way for public use. All private residential streets shall be designed, built, and dedicated as shown on the approved General Development Plan in accordance with standards set forth in the following section.
140	2.032 Private Residential Street Standards
141 142 143	The plans for all private residential streets shall be prepared and/or certified by a registered engineer or surveyor and shall meet the following standards:
144	(a) Drainage
145 146 147 148	Objective: The roadway shall be aligned and constructed such that adequate drainage is provided from the surface and subsurface of said roadway, as well as across said roadway from adjacent property.
149 150 151 152	Standards: Minimum storm sewer or drainage way Capacity - 10 year storm Minimum cross drainage Capacity - 25 year storm
153	(b) Width and alignment:
154 155 156 157 158	Objective: The roadway, including shoulders, shall be of sufficient width and design to provide for travelways, emergency pullover space, parking space, and a berm or shoulder adequate to accommodate expected traffic conditions.
159 160 161 162 163 164	Further, the alignment of said roadway including grades, horizontal curves, vertical curves, and the super elevation in each curve shall be designed to provide for safe traffic movement at the intended design speed as well as to provide for slight distance which will insure adequate stopping time.

Standards:

	Max. No. of	Minimum Surface V	₩; d+h		M ¥	Desi on	stopping
Type Street	Served (D.U.)	No Curb	Curb	Surfacing	Grade	Speed	Dist.
Cul-de-sac or loop	less than 15 D.U.	201	20'	Gravel	15%	20 mph	100'
Residential street	15-60 D.U.	201	24'	Pavement	12%	30 mph	200'
Residential collector	greater than 60 D.U.	20'	28 '	Pavement	8%	35 mph	250 '
		•					

165	Minimum Width of Shoulder of Berm:	
166 167 168	Ditch = 6' shoulder Swale = 4' shoulder Curb = 3' berm	
169	(c) Intersections:	
170 171 172 173 174	Objectives: All intersections shall be well marked and shall have an adequate stopping sight distance. Grades at intersections should be minimized and the angle of intersecting streets should be as close to 90 degrees as possible.	
175	Standards:	
176 177	Minimum angle of 60 degrees Maximum grade at intersection 5 percent	
178	(d) Material and Procedure Specifications:	
179 180 181	All bridges, culverts, curbing, surfacing materials, and construction practices and procedures shall meet D.O.T. speficiations.	
182 #183 184 185	Where a gravel surface is permitted pursuant to Section 2.032 (b) above, the procedure and materials shall be the same as those prescribed by D.O.T. for hard surfaced streets except that the paved surfacing may be omitted.	
186 187 188 189 190 191 192	All street plans shall be reviewed by the County Engineer prior to approval of the General Development Plan. The Board may, upon written application of the subdivider, grant minor variances from stated standards provided said variances are consistent with the stated objectives. Prior to considering said application the Board shall refer it to the staff and County Engineer for comment.	
193	2.033 Private Minor Streets	
194 195	Certain streets and rights-of-way may be designated as private minor streets if:	
196 197 198	(a) The proposed street provides access to no more than four lots, proposed or existing, and intersects with a public street; and	
199 200	<pre>(b) Provisions satisfactory to the Board or its staff are made for:</pre>	
201	(1) Continuing common use of the street by	

203 204	(2) Access for public service and emergency vehicles; and
205 206 207	(3) Continuing private maintenance of said street to provide for safe passage of expected traffic.
208 209 210 211 212 213 214	An easement or right-of-way at least 30 feet wide for the full length of the street must be provided and additional width may be required by the Board if necessary for drainage or utilities. Said street shall be located, designed, and built such that it provides a safe intersection with a public street and safe passage of public service and emergency vehicles.
215	2.04 Conformity to Surrounding Development
216 217 218 219	The proposed street layout within a subdivision shall be coordinated with the existing street system of the surrounding area and, where possible, existing principal streets shall be extended.
220 221 222 223 224 -225	No existing access to adjacent properties may be closed which would render said adjacent property inaccessible, unless other arrangements are made to render comparable access to said property. In no case shall a subdivision be developed such that an adjacent property becomes completely unaccessible.
226	2.05 Frontage Streets
227 228 229 230 231 232 233	Where a subdivision adjoins a heavily traveled street, in the interest of highway safety, the subdivider may be required by the Board to provide either a frontage street parallel to said heavily traveled street or reverse frontage on a smaller street. Where reverse frontage is required, private driveways shall not have direct access to said heavily traveled street.
234	2.06 Pedestrian Ways
235 236 237 238	Streets shall be designed or walkways provided to assure safe and reasonable access to parks, playgrounds, schools, and other places of public assembly. Crosswalks may be required by the Board.
239	2.07 Blocks
240 241	. The length, width and shape of blocks shall be designed to provide for the following:
242 243	(a) Adequate building sites for the proposed use; and

244 245	(b) Needs for vehicular and pedestrian circulation; and
246	(c) Control and safety of traffic; and
247 248 249 250 251	(d) Convenient access to scenic overlooks and water areas. However, at no time shall block lengths exceed one thousand four hundred (1,400) feet or be less than four hundred (400) feet.
252	2.08 Service Ways
253 254 255 256	Service ways and/or fire lanes shall be provided for all lots designed for commercial or industrial purposes and shall be adequate to provide reasonable access for all necessary service vehicles.
257	3. Names of Subdivisions and Streets
258 259 260	The name of a subdivision shall neither duplicate nor closely approximate the name of an existing subdivision with the County.
261 262 263 264 265 266 267	Proposed streets which are obviously in alignment with existing streets shall be given the same name as the existing street. The assignment of new names is subject to Board approval, and duplication of existing names, phonetically or otherwise, shall be avoided. Street markers of a design approved by the Board shall be installed at each intersection in uniform locations.
268	4. Water and Sewer Systems
269 270 271 272 273 274 275 276 277	The General Development Plan shall be accompanied by evidence satisfactory to the Board of the proposed method and system of water supply and sanitary sewage collection and disposal for all lots intended for a use requiring domestic water supply and/or sanitary sewer. Except in the case of individual septic tanks, the installation of all said sytems, in accordance with plans to be approved as set forth below, shall be required prior to final plat approval unless otherwise permitted pursuant to Article V.
278	4.01 Public Systems
279 280 281	Where the proposed system is to be connected to one or more public systems, as defined in Appendix B, the General Development Plan shall be accompanied by a complete set of

construction plans for the proposed system. Said plans shall have been approved by the engineer of the public system(s)

and any appropriate State agency prior to their approval by

the Board.

286 4.02 Community Systems

Where the proposed system is a community system as defined in Appendix B, the General Development Plan shall be accompanied by the approval of, and documents required by, the appropriate agency as set forth in Appendix B. If, at any time, the proposed system is to be connected to any public system, all requirements of Section 4.01 above, shall apply.

293 4.03 Individual Systems

294

295 296

297

298

299

300

301

302

303 304

316

322

323

Where the proposed system is an individual system, as defined in Appendix B, the General Development Plan shall be accompanied by the approval of the Craven County Health Department and shall show that the subdivider has complied with all ordinances and regulations of the Craven County Board of Health and applicable State law. The statement from the Health Department shall show that each lot has adequate land area and soil conditions suitable to accommodate the proposed methods of water supply and sewage disposal and shall be based upon a field investigation as approved by the Craven County Health Department.

305 4.04 Public System Extensions

The Board may require any lot to be served by public water and/or sewer systems if such service can reasonably be provided by extending existing systems.

309 4.05 Fire Hydrants

Where a water line six inches or greater in diameter is required in a public or community system, fire hydrants shall be installed on said line. The hydrants shall be spaced so that coverage to all building sites along said line may be provided with not more than 500 feet of hose and shall be located to facilitate access, hose laying and drainage.

5. Storm Water Drainage

The General Development Plan shall be accompanied by evidence satisfactory to the Board as to the proposed method of providing for storm water drainage. It shall be the responsibility of the subdivider to provide a drainage system which is designed to meet the following objectives:

- (a) Provide for adequate drainage from all roads, parking lots, and other developed areas; and
- 324 (b) Provide a suitable building area on each lot 325 intended for building development which is safe from 326 inundation, erosion, or subsidence; and

- 327 (c) Prevent both the unneccessary impoundment of 328 natural drainage ways and the creation of areas of 329 standing water; and
- 330 (d) Insure that existing drainage ways serving 331 adjacent properties are maintained; and
- 332 (e) Insure that natural runoff levels are not 333 substantially increased in order to prevent harmful 334 flooding downstream and to maintain desirable 335 groundwater levels; and
- 336 (f) Prevent inundation of surface water into sanitary sewer systems; and
- 338 (g) Protect all roads, driveways, utilities and 339 other types of development from damages caused by 340 improper drainage control.
- 341 The design of said system shall be subject to approval 342 of the Board and the installation of said system shall be 343 required prior to final plat approval pursuant to Article V 344 of this Ordinance.
- 345 Easements for all drainage ways shall be provided as required by Article IV, Section 2.02 of this Ordinance. The 346 -347 Board shall have the authority to require curb and gutter, underground drainage, and other improvements it finds 348 349 necessary to meet the above objectives. In all subdivisions outside an incorporated municipality with new street right-of-way to be dedicated to the public, the District 350 351 352 Engineer of D.O.T. must review and certify his approval of 353 drainage plans pursuant to Article V, Section 4.02 of this 354 Ordinance.

355 6. Sedimentation Control

364

In order to prevent soil erosion and sedimentation pollution of streams, springs, flat water bodies, or other drainage networks, the subdivider shall show proof of an erosion and sediment control plan which has been approved by the State or local agency having jurisdiction in accordance with The Rules and Regulations for Erosion and Sediment Control as adopted by the North Carolina Sediment Control Commission, April, 1974, as amended.

7. Surveying and Placement of Monuments

"The Manual of Practice for Land Surveying", as adopted by the North Carolina Board of Registration for Professional Engineers and Land Surveyors, under provisions of Chapter 89 of the North Carolina General Statutes, shall apply when conducting surveys in order to determine the accuracy for

370 surveys and placement of monuments, control corners, markers, 371 and property corner ties, and to determine other standards 372 and procedures governing the practice of land surveying for 373 subdivisions. 374 8. Air Quality As required by Chapter 143, Article 21, of the North Carolina General Statutes, all subdivisions of more than 500 375 376 377 units at a density of more than 7,680 persons per square mile (12 persons/acre) shall show proof of compliance with Air 378 379 guidelines established by the Environmental 380 Management Commission of North Carolina Department of Natural 381 and Economic Resources. 382 9. Other Improvements The subdivider is encouraged to consider this section as 383 he develops plans for any subdivision. Furthermore, the 384 Board shall recommend to the Board of Commissioners policies 385 and standards relating to the location, design, installation, 386 and reservation of the following: 387 388 Underground .electrical, telephone, 389 television, and other distribution lines; and 390 Measures providing for safe pedestrian (b) movement throughout the subdivision either within the 391 392 street right-of-way or within reserved pedestrian ways; 393 and 394 lighting intersections; Outdoor at 395 turnarounds; or other locations; and 396 Areas of significant scenic, historical, 397 cultural, or ecological value; and (e) Land for recreation, school sites, or other 398 399 public facilities. 400 ARTICLE IV 401 DESIGN STANDARDS 402 THE FOLLOWING STANDARDS SHALL BE CONSIDERED AS MINIMUM 403 REQUIREMENTS FOR ALL SUBDIVISIONS OR RESUBDIVISIONS: 404 l. Lots 405 The lot size, width, depth, shape, orientation, and building setback lines shall be appropriate for the location 406

10

of the subdivision and for the type of development and use

contemplated and shall be sufficient to accommodate proposed

407

408

409

utilities.

410 1.01 Single-Family Residential Lots

Any lot(s) in a subdivision intended for the development of a detached, single-family dwelling unit(s) shall comply with the following requirements:

414 1.011 Area

In order to provide adequate land area and to accommodate the use of septic tanks and private sources of water in a safe, healthful manner, the following requirements shall be met:

419 420			Minimum Lot Area	<u>.</u>	Appı	cox.
421 422 423	(a)	Lots served by both public sewer and public water	8,000 sg.	ft.	1/5	acre
424 425 426	(b)	Lots served by only public sewer	10,000 sq.	ft.	1/4	acre
427 428 429	(c)	Lots served by only public water	20,000 sq.	ft.	1/2	acre
430 431 432 433	(d)	Lots served by neither public sewer nor public water	30,000 sq.	ft.	3/4	acre

434 (Community water or sewer systems as defined in Appendix B 435 are considered "public" systems in this Section).

436 The Craven County Health Department must, according to State 437 law and Ordinances of the Craven County Board of Health, 438 require larger lot sizes if necessary to protect public 439 health and insure proper operation of septic tanks and wells. The Board may, upon application of the subdivider, permit lots smaller than the minimums set forth herein, provided 440 441 442 that the proposed smaller lot size is approved by the Craven 443 Even though said Department Health Department. 444 approves said proposed smaller lot size, the Board is not 445 required to approve said application.

1.012 Width

446

Each lot shall have a minimum width of 70 feet across the center of the proposed building site and a minimum at the street right-of-way line of 70 feet. In the event the lot fronts on a cul-de-sac, the minimum lot width fronting on the

1	
451 452 453 454	street may be 35 feet. However, a minimum of 25 feet may be permitted at the street right-of-way at the discretion of the Board. Corner lots shall have an extra width of 10 feet to permit adequate setback from side streets.
455	1.013 Depth
456 457 458 459 460 461 462	Each lot shall have an average depth of at least one hundred (100) feet. For any lot of less than one acre, the average depth shall be no greater than 2.5 times its average width, except where that portion of the lot which exceeds this requirement (1) is used for easements, or (2) is set aside for the purpose of providing a buffer area, or (3) is an area which is in some way unsuitable for development.
463	1.014 <u>Setbacks</u>
464 465	Each lot shall contain a suitable building site which shall lie within the following building setback lines:
466 467	Distance from center line of existing State maintained streets (not meeting D.O.T. standards) 60 feet
468 469	Distance from front right-of-way line on all other streets 30 feet
470	Distance from side property line 10 feet
471	Distance from side property line abutting street 20 feet
472	Distance from rear property line 25 feet
473 474 475 476	Said setback distance requirements may be reduced by the Board provided that evidence found satisfactory by the Board is submitted by the subdivider to the Board which insures that any structure erected on said site shall:
477 478	(a) Be adequately buffered from the adjoining street to insure safety and reduction of noise; and
479 480	(b) Not impede sight distance on curves and at intersections; and
481 482 483	(c) Be adequately buffered or be a suitable distance from any structure on an adjoining lot to insure privacy and adequate circulation; and
484	(d) Not encroach on any property line.
485	1.02 Multi-Family Residential Lots
486 487	Each lot intended for the development of more than one dwelling unit, shall have a minimum lot size of 12,000 square

- feet and shall have at least 3,000 square feet of lot per 488
- dwelling unit. The standards set forth in Section 1.01 of 489 490 this Article, except those standards set forth in Section
- 491 1.011 (a) and (b), shall also apply.
- 492 1.03 Commercial or Industrial Lots
- 493 Each lot intended for commercial or industrial purposes,
- 494 shall be of a sufficient size to accomodate anticipated
- 495 parking and service needs. The standards set forth in Section
- 1.01 of this Article, except those standards set forth in Section 1.011 (a) and 1.014 shall also apply. 496
- 497
- 498 2. Easements
- 499 Easements shall be provided as follows:
- 2.01 Utility Easements 500
- 501 Easements for utilities shall be provided, preferable
- 502 centered on rear or side lot lines, and shall be at least
- 503 fifteen (15) feet in width.
- 504 2.02 Drainage Easements
- 505 An easement shall be reserved by the subdivider or
- otherwise provided conforming with the lines of any 506
- 507 drainageway into which natural drainage has been diverted.
- 508 Said drainageway shall be of sufficient width to carry storm
- water runoff from a 10 year storm. 509
- 510 2.03 Buffer Strip
- 511 The Board may require a buffer strip no more than ten
- 512 (10) feet wide adjacent to a major street or a commercial or
- industrial development. The Board may also require the subdivider to arrange for, or be responsible for, the 513
- 514
- 515 planting and maintenance of said buffer strip.
- 516 ARTICLE V
- 517 PROCEDURE FOR REVIEW AND APPROVAL OF SUBDIVISION PLATS
- 518 1. General
- 519
- To secure approval of a plat, as required by this Ordinance, the subdivider shall follow procedures set forth 520
- in this Article. A minor subdivision (defined in Section 2 of this Article) may be approved pursuant to Section 2 of 521
- 522
- 523 All other subdivisions shall be approved this Article.
- 524 pursuant to Sections 3, 4, 5, and 6 of this Article.

In the event a plat falls within one of the exceptions to the definition of a subdivision, such excepted plat shall be accompanied by a statement from the County Planning Director to that effect and shall be duly noted on the plat.

529 2. Minor Subdivisions

Procedures for handling applications for approval of minor subdivisions are intended to simplify the processing of routine small subdivisions with due regard to the protection of the public interest.

A minor subdivision is the division of a tract of land into no more than four (4) lots with access to be provided either from an existing public street or from a private minor street (defined in Article III, Section 2.03).

Where the subdivider intends to develop a minor subdivision he may apply for final approval through the procedures set forth in Section 2.01. Said intent shall be stated, in writing, in a form acceptable to the Board and signed by the subdivider.

543 2.01 Procedure for Approval

553

554

555

556

557

Final approval of a plat for any minor subdivision may 545 be granted by the staff of the Board, which has been 546 designated a planning agency by the Craven County 547 Commissioners pursuant to North Carolina General Statute 548 153A-321, subsequent to the following procedure.

- (a) The subdivider shall submit two (2) copies of a surveyed plat meeting the requirements of Section 6.01 of this Article. Further, he shall provide satisfactory evidence describing the following:
 - Methods of providing a water supply and sewage disposal to each lot, including any State or local approvals which may be needed; and
 - 2. Methods of providing access to each lot including the name of any new street; and
- 3. Methods of providing for adequate drainage.
- (b) The staff shall review said minor subdivision and shall find that it either does or does not meet the requirements of this Ordinance and what improvements, if any, will be required by this Ordinance. (See Section 5 of this Article).

(c) If it is found that improvements will be required the subdivider shall submit three additional copies of said plat describing the plans for said improvements. Upon approval of said plans by the staff, a copy shall be forwarded to the Director of Public Safety who shall, upon completion and installation of said improvements, inspect said minor subdivision and shall certify that all improvements either have or have not been installed in accordance with said plans and the requirements of this Ordinance.

Note: At this stage, the subdivider may post improvement guarantees pursuant to Section 5 of this Article and receive final approval of his subdivision plat.

- (d) Once said subdivision has been approved and it is found that no additional improvements are required, or if additional improvements are required and have been certified by the Director of Public Safety, the staff shall then certify final approval in writing on all copies of said subdivision plat. One copy shall be recorded with the minutes of the Board and the approved surveyed plat shall be returned to the subdivider who shall record said plat with the office of the Craven County Register of Deeds within 30 days of receipt. Failure on the part of the subdivider to record said plat within said 30 days shall render said approval null and void.
- (e) Decisions of the staff may be appealed at any time by the subdivider to the Board. If an appeal is made, it shall be heard and decided by the Board at its next regularly scheduled meeting, provided that, if the Board finds that sufficient information is not available to it, the Board may continue the hearing and/or postpone its decision for no more than 32 days.

599 3. <u>Subdivisions</u>

÷589

Where the subdivider intends to divide a tract into 5 or more lots he shall receive final approval from the Board subsequent to procedures set forth in the remaining sections of this Article.

3.01 Preliminary Application

In order to initiate discussions between the subdivider and the Board early in the design process, the subdivider shall submit for all subdivisions, other than minor subdivisions, a preliminary application to the Board or its staff prior to preparing the general development plan.

610 Said application shall include:

- (a) A vicinity map at a scale of l" = 400' locating said subdivision in relation to the surrounding area showing the boundaries of the entire tract(s) ultimately to be subdivided and the boundaries of that portion of the tract to be developed initially; and
- (b) A preliminary application form containing all information required by the Preliminary Application as found in Appendix C.
- The Board or its staff shall review said application with the subidivider so that each shall know what is expected.

622 3.02 Preliminary Site Plan

The Preliminary Site Plan shall show at least that portion of the subdivision that the subdivider plans to develop at this time.

626 If the subdivider intends to divide the entire tract into 15 or more lots he shall also submit 5 copies of a 627 preliminary site plan at least 14 days prior to a regularly 628 scheduled meeting of the Board at which said plan is to be 629 considered, although said time limit may be waived at the 630 631 Although not required, it is discretion of the Board. 632 suggested that a preliminary site plan be submitted for all 633 subdivisions to insure that preliminary plans are correct 634 prior to preparing extensive engineering details.

Said preliminary site plan shall be at a scale of at least 1" = 200' and contain all information required in the Preliminary Site Plan Check list as found in Appendix D.

The Board shall review and either approve, approve conditionally, or disapprove each preliminary site plan. First consideration shall be at the first regularly scheduled meeting after the plan is submitted, pursuant to Section 3.01 above. The Board shall take action on the preliminary site plan within thirty-two (32) days of its first consideration.

644 4. General Development Plan

635

636

637

638 639

640 641

642

643

645

646

647

648 649

650

651

652

For every subdivision except minor subdivisions, a General Development Plan, containing all required information, shall be submitted to the Board at least fourteen (14) days prior to the regular meeting at which said plan is to be considered although said time limit may be waived at the discretion of the Board. Six copies of said plan shall be required, provided that additional copies may be required by the Board or its staff, if needed.

653 4.01 Contents Required

The General Development Plan shall include the site plan 655 (as required by Section 3.02 of this Article) in its final 656 form as well as all other information required by the General 657 Development Plan Checklist as found in Appendix E of this 658 Ordinance.

659 In addition, the Board may, under the authority of the 660 the Filing Resolution Requiring County 661 Environmental Impact Statement, adopted and pursuant Chapter 113A of the North Carolina General Statutes, require 662 663 Environmental Impact Statement for any subdivision 664 exceeding two acres in size.

4.02 Review Procedure

665

666 667 668

669

670

671

672

673

674

675

676

677 678 679 The Board shall review and either approve, approve conditionally, or disapprove each General Development Plan. First consideration of said plan shall be at the next regularly scheduled meeting of the Board after the plan is submitted pursuant to Section 4.01, above. The Board shall take action on the General Development Plan within thirty-two (32) days of its first consideration or at the next regularly scheduled meeting after receiving responses from the public reviewing agencies enumerated below.

Before final action on any General Development Plan is taken by the Board, copies of said plan shall be referred by the Board to those public agencies concerned with new development for review and comment. Said agencies shall include, but are not limited to, the following:

- 680 (a) District Engineer of D.O.T. regarding streets 681 and drainage; and
- 682 (b) Craven County Health Department and/or other 683 appropriate departments and agencies (See Appendix B) 684 regarding sanitary sewer and water systems; and
- 685 (c) Soil Conservation Service U.S.D.A., regarding 686 sedimentation, drainage, and the suitability of the site 687 for development; and
- 688 (d) Craven County Board of Education regarding school site reservations, if any; and
- 690 (e) Craven County Parks and Recreation Advisory 691 Commission regarding dedications of open space and/or 692 recreational sites, if any.
- 693 Where this Ordinance requires proof of approval from 694 other State or local agencies, the following certificates

695 (substantially consistent in form to those shown in Appendix 696 G) shall be received by the Board prior to final approval of 697 any General Development Plan: (a) A certificate signed by the appropriate D.O.T. 698 official stipulating that the plans for any proposed 699 700 street system to be dedicated to the public outside any 701 incorporated municipality are approved. 702 A certificate signed by the appropriate municipal official stipulating that the plans for any 703 704 proposed street systems to be dedicated to the public in 705 said municipality are approved; 706 A certificate(s) signed by the appropriate State and/or local official(s) (indicated in Appendix B) stipulating that the plans for water supply and/or sewage disposal systems proposed for installation meet 707 708 709 710 all pertinent requirements and are approved; and 711 (d) A certificate signed by the appropriate State or local official stipulating that the erosion and 712 713 sedimentation control plan is approved. 714 If the Board approves the General Development Plan, such 715 approval shall be indicated on three copies by the following certificate signed by the Chairman or other authorized member 716 717 of the Board: "Certificate of Approval by the Subdivision Review Board" 718 719 This certifies that the Craven County Subdivision Review 720 Board approved the General Development Plan for 721 Subdivision at its meeting on the 722 723 Chairman, Craven County Sub-724 Date 725 division Review Board 726 One (1) copy shall be transmitted to the Director of 727 Public Safety, one (1) copy shall be returned to the 728 subdivider, and one (1) copy shall be retained by the Board. 729 If the Board disapproves or approves conditionally said plan, the reasons for such action shall be stated in writing 730 731 and entered in the records of the Board. The subdivider may 732 make changes and submit a revised plan which revision shall 733 be submitted, reviewed, and acted upon by the Board pursuant 734 to this section. 735 Approval of the General Development Plan shall be valid 736 for one (1) year unless a written extension is granted by the

737 Board on or before the one (1) year anniversary of said approval. If the final plat is not submitted for approval

739 within said one (1) year period or any period of extension,

740 the said approval of the General Development Plan shall be 741 null and void.

742 5. Improvements Installation or Guarantees

743 Upon approval of the General Development Plan by the 744 Board, the subdivider may proceed with the installation of or 745 arrangement for required improvements. Required improvements 746 include the following:

- (a) Street access to each lot; and
- (b) A water supply for each lot; and
- 749 (c) A sewage disposal system (exempting septic 750 tanks) for each lot; and
- 751 (d) Any required drainage or sedimentation control facilities; and
- 753 (e) Street markers; and

747

748

766

767

768

769

770 771

772

773 774

775

- 754 (f) Fire hydrants, where required; and
- 755 (g) Any corrective measures required pursuant to Article III, Section 1.

757 5.01 Completion of Improvements

Except as provided in Section 5.02, below and prior to final plat submission or approval, the subdivider shall complete, install, and dedicate all required improvements as specified on the approved General Development Plan for that portion of the subdivision to be shown on the Final Plat. The subdivider shall certify the dedication of said improvements in accordance with Section 5.032 of this Article.

765 5.02 Improvements Guarantees

5.021 Agreement and Guarantees Required

In lieu of requiring the completion, installation and dedication of all improvements prior to Final Plat approval, the Board may enter into an agreement with the subdivider whereby the subdivider shall agree to complete all required improvements as specified by the approved General Development Plan for that portion of the subdivision to be shown on the Final Plat. Once said agreement is signed by both parties, the Final Plat may be approved by the Board. To secure this agreement,

the subdivider shall provide, subject to the approval of the Board, either one, or a combination of, the following guarantees:

(a) Surety Performance Bond(s)

The subdivider shall obtain a performance bond(s) from a surety bonding company authorized to do business in North Carolina. The bond(s) shall be payable to the County of Craven and shall be in an amount equal to 1.25 times the entire cost, as estimated by the subdivider and proved by the Director of Public Safety, of installing all required improvements. The duration of the bond(s) shall be until such time as the improvements are accepted by the Board pursuant to Section 5.022 of this Article, but for not more than one year with the possibility of one time extension.

(b) Cash or Equivalent Security

The subdivider shall deposit cash or other instrument readily convertible into cash at face value, either with the County or in escrow with a financial institution designated as an official depository of of County. The use of any instrument other than cash shall be subject to the approval of the Board. The amount of deposit shall be equal to 1.25 times the cost, as estimated by the subdivider and approved by the Director of Public Safety, of installing all required improvements.

If cash or other instrument is deposited in escrow with a financial institution as provided above, then the subdivider shall file with the Board an agreement between the financial institution and himself quaranteeing the following:

- 1. That said escrow account shall be held in trust until released by the Board and may not be used or pledged by the subdivider in any other matter during the term of the escrow; and
 - 2. That in the case of a failure on the part of the subdivider to complete said improvements, the financial institution shall, upon notification by the Board, immediately either pay to the County of Craven all funds in said account, or deliver to the County any other instruments fully endorsed or otherwise made payable in full to the county.

821 5.022 Release of Guarantee Security 822 The Board may release a portion of any security 823 posted pursuant to Section 5.02 of this Article, as the 824 improvements are completed and recommended for approval 825 pursuant to Section 5.03 of this Article. thirty-two (32) days after receiving the certificates 826 827 required by Section 5.03 of this Article, the Board shall approve or not approve said improvements. If the 828 approves said improvements, then it shall 829 830 immediately release any security posted pursuant to Section 5.02 of this Article. 831 5.023 Substantial Compliance with Forms in Appendix G 832 833 Forms for agreements, performance bonds, letters of credit, escrow account, or cash equivalents authorized 834 835 Section 5.02 of this Article shall 836 substantially to the forms prescribed in Appendix G, 837 Sections 4, 5, and 6. 5.03 Inspection and Certification 838 839 5.031 Certificate of Improvements 840 The Director of Public Safety or other qualified person designated by the Board shall regularly inspect 841 842 construction of required improvements. 843 completion of these improvements, said inspector shall 844 file with the Board a statement (1) certifying that said 845 improvements have been either completed as required, or completed as required except for certain listed minor 846 defects, and (2) recommending the approval of said 847 848 improvements. (See Appendix G). 849 5.032 Subdivider's Certificates 850 Upon completion of the required improvements, the 851 subdivider shall file with the Board the following 852 certificates: 853 (a) Certificate of Completion and Warranty 854 The certificate of completion and warranty 855 shall stipulate the following: (See Appendix G). 856 That all improvements required by this 857 Ordinance have been completed; and 858 That these improvements are in compliance with the minimum standards specified by this 859 860 Ordinance for their construction; and

861 862 863 864 865 866	3. That the subdivider knows of no defects from any cause and that he will warrant all improvements against defects in materials and workmanship for a period of one year after the Certificate of Completion and Warranty is executed; and
867 868 869 870 871 872	4. That in the event any defects are discovered in materials or workmanship in any required improvements during the warranty period, the subdivider will, at his expense, replace and/or repair said defects to the satisfaction of the Board.
873	(b) Certificate of Dedication and Maintenance
874 875	The certificate of dedication and maintenance shall stipulate the following (See Appendix G):
876 877 878	 That all property and improvements are owned by the subdivider and are free of any encumbrance or lien except as enumerated; and
879 880 881 882 883 884 885	2. That the subdivider has freely dedicated or reserved all required rights-of-way, easements, streets, utilities, open spaces, or other improvements to public or private use as noted on the approved General Development Plan and has freely established minimum building setback lines; and
886 887 888 889 890	3. That the subdivider shall be responsible for the maintenance of all improvements until either said improvements are taken over the the appropriate public agency or arrangements satisfactory to the Board have been made for maintenance of said improvements.
892 893 894 895 896 897	Both of said certificates shall be filed with the Final Plat except when improvements guarantees are used. When said guarantees are used, said certificates shall be filed with the Board when improvements are completed and shall be forwarded to the Register of Deeds to be recorded either with the Final Plat or as separate documents.
899	5.033 Form of Certificates
900 901 902 903	Certificates required pursuant to Subsections 5.031 and 5.032 of this Article shall conform substantially to the certificate forms prescribed in Appendix G, Sections 1, 2, and 3.

904 6. Final Plat

908

909

910

911

912 913

917

918

936

937

938

939

940

941

942

943

944 945 946

905 The Final Plat shall constitute only that portion of the 906 subdivision which the subdivider proposes to record and 907 develop at that time.

Once the Board has either approved all required improvement or has entered into an improvements quarantee agreement with the subdivider than the Final Plat may be approved by the Board. The subdivider shall submit four (4) copies and one (1) original of said plat to the Board no less than fourteen (14) days prior to the regular Board meeting at 914 which it shall be considered for approval, although said time 915 limit may be waived at the discretion of the Board. Said plat 916 shall be submitted not more than twelve (12) months after the date on which the General Development Plan was approved, unless a written extension of this time limit is granted by 919 the Board on or before the one-year anniversary of the 920 approval of the General Development Plan.

921 6.01 Contents Required

The original of the final plat shall be prepared on linen or film by a registered land surveyor, licensed to 922 923 924 practice in the State of North Carolina. Said plat shall 925 conform to the provisions of North Carolina General Statute Section 47-30 as amended. Further, said plat shall be fifteen (15) inches by twenty (20) inches or twenty (20) inches by thirty (30) inches and of a scale not less than one 926 927 928 929 inch equals two hundred feet (1" = 200').

930 The Final Plat shall depict or contain all information 931 required in the Final Plat Checklist as found in Appendix F 932 of this Ordinance.

933 6.02 Review Procedure

934 The Final Plat shall be reviewed according to the 935 following procedure:

First consideration shall be at the next regularly scheduled meeting of the Board after the Final Plat is submitted pursuant to Section 6.01 of this Article. Board shall approve or disapprove the Final Plat at its first consideration within thirty-two (32) days of its first consideration by the Board.

During its consideration of the Final Plat, the Board may appoint such qualified persons as it deems necessary to confirm the accuracy of the Final Plat. If substantial errors are found by the Board, the plat shall not be approved until such errors have been corrected by the subdivider.

947 If the Board approves the Final Plat, such approval shall be indicated on the original and each copy of the plat 948 949 by the following certificate signed by the Chairman or other 950 authorized member of the Board: 951 "Certificate of Approval by the Subdivision Review Board" 952 This certifies that the Craven County Subdivision Review 953 Board approved the Final Plat of the 954 the Subdivision at its meeting on 955 956 957 Chairman, Craven County Subdivision Date 958 Review Board 959 If the Board disapproves the Final Plat, the Board shall 960 state in writing its reasons for such action, specifying the 961 provisions of this Ordinance with which the plat does not comply. One copy of this statement shall be transmitted to the subdivider within fifteen (15) days of disapproval; one copy shall be retained by the Board as a part of its 962 963 964 965 proceedings, and one copy shall be sent to the Register of 966 If the final plat is disapproved, the subdivider may 967 make such changes as needed to bring the plat into compliance with the provisions of this Ordinance and resubmit the same for reconsideration by the Board pursuant to the procedures 968 969 970 set forth in this Section. 971 6.03 Effect of Plat Approval on Dedications 972 The approval of a Final Plat shall not constitute or 973 effect the acceptance by the County of the dedication of any 974 land, utility line, or other facility shown on said plat. 975 6.04 Disposition of Copies 976 If the Final Plat is approved by the Board, such 977 approval shall be noted on the original tracing of said plat 978 and on four (4) copies as required by Section 6 of this 979 Said original tracing shall be recorded by the subdivider with the Craven County Register of Deeds within thirty (30) days after final plat approval or said approval 980 981 982 shall be null and void. The remaining prints shall be 983 distributed as follows: 984 (a) Board of Commissions - 1 copy 985 (b) Director of Public Safety - 1 copy

986 (c) The subdivider - 1 copy

987 (d) Subdivision Review Board 1 copy

988 6.05 Resubdivison Procedures

989 For any replatting or resubdivision of land, the same 990 procedures and requirements shall apply as prescribed in this 991 Ordinance for an original subdivision.

992 7. Variances

993 Where a subdivider can show that strict adherence to a 994 provision(s) of this Ordinance would, because of conditions 995 peculiar to the site, cause an unnecessary hardship, the subdivider may submit a written application to the Board of 996 997 Commissioners for a variance from said provision(s) . Said 998 application may be delivered by the subdivider either to the 999 Board (or its staff) or to the Board of Commissioners who shall refer it immediately to the Board for consideration and 1000 recommendation. The Board shall consider said application 1001 1002 within thirty-two (32) days of its submission and within that 1003 time, shall recommend inwriting to the Board 1004 Commissioners that said Commissioners either approve or not approve the application. Said recommendation shall state the reasoning upon which it is based. By its second regular meeting after receipt of the Board's recommendation, the 1005 1006 1007 1008 Board of Commissioners shall either approve or not approve 1009 said application, provided that approval of said application 1010 shall be given only the the extent that the Board of 1011 Commissioners finds to be absolutely necessary and not to an 1012 extent which would violate the terms of this Ordinance. If 1013 the application is approved and a variance granted by the 1014 Board of Commissioners, said approval and the basis therefor 1015 shall be entered in the minutes of the Commissioners.

1016 8. Amendments

The Board of Commissioners may from time to time amend the terms of this Ordinance, pursuant to North Carolina General Statute 153A-323, but no amendment shall become effective unless it shall have been proposed by, or shall have been submitted to, the Board for review and recommendation.

1023 ARTICLE VI

1024 SUBDIVISION REVIEW BOARD

1025 l. Board Established

There is hereby established the Craven County 1027 Subdivision Review Board, designated by the Craven County

1028 Commissioners as a planning agency pursuant to North Carolina General Statute 153A-321, and known in this Ordinance as the 1029 1030 "Board". 1031 2. Powers and Duties 1032 Pursuant to the requirements and procedures set forth in 1033 this Ordinance, the Board shall have the following powers and 1034 duties: consider 1035 (a) To and review all proposed 1036 subdivisions of land within the subdivision jurisdiction 1037 of this Ordinance; and 1038 disapprove said proposed \mathbf{To} approve or 1039 subdivisions; and 1040 To enforce the provisions of this Ordinance through legal action, if necessary; and 1041 To review and make recommendations to the 1042 1043 Board of Commissioners regarding proposed variances from 1044 and amendments to the Ordinance; and 1045 To enter into contracts and agreements 1046 authorized in this Ordinance and to enter into such 1047 other contracts and agreements as the Board of 1048 Commissioners may approve. 1049 Membership 1050 Board shall be appointed by the Board of Commissioners, and shall consist of seven members. Said members shall be appointed from the following groups or 1051 1052 1053 classes: 1054 (a) Three citizens-at-large; and (b) Four experts whose primary field of employment 1055 or area of expertise in any of the following: engineer, 1056 real estate developer, architect, finance, real estate 1057 sales, water and air quality, surveyor, land planner or 1058 1059 landscape architect. 1060 Terms Three members of the Board shall be appointed for an 1061 1062 initial term expiring , and four members of the Board shall be appointed for an initial term expiring 1063 1064 Thereafter each term shall be for a four 1065 of period years and shall expire Each member shall serve until a 1066 successor is appointed. Vacancies shall be filled by the 1067

Board of Commissioners by appointment for the duration of any unexpired term. No person may be appointed to serve more

1070 than two consecutive terms.

1071 5. Chairman

The Board of Commissioners shall appoint one of the 1072 1073 members of the Board to serve as Chairman. The initial term 1074 of the Chairman shall be through 1075 Thereafter, the Board of Commissioners shall appoint the 1076 for years Chairman period of two to a No member may be appointed to 1077 serve more than two consecutive terms as Chairman. A vacancy 1078 1079 in the position of Chairman shall be filled by appointment of 1080 one of the members of the Board by the Board of Commissioners to fill the unexpired term. 1081

The Board shall select its own Vice-Chairman to preside or act in the event of the absence or incapacity of the Chairman. The provisions of the preceding paragraph with respect to the term and succession of the Chairman shall also apply to the Vice-Chairman.

1087 6. Meetings

1082

1083 1084 1085

1086

The Board shall establish a regular time and place to meet, provided that it shall meet at least once a month. Either the Chairman or Vice-Chairman may call special meetings as he deems necessary upon two days actual notice, oral or written. A quorum of the members of the Board must be present in order to transact business, and a majority of the members shall constitute a quorum. All meetings shall be open to the public.

1096 7. Attendance at Meetings by Board Members

If any member is absent from three consecutive regular meetings which are unexcused by the Chairman of the Board, then said Chairman shall notify the Board of Commissioners. Upon receipt of said notification, the Board of Commissioners may declare a vacancy on the Board and may appoint a new member for the remainder of the term.

1103 8. Conflicts by Board Members

Any Board member shall be disqualified from considering, reviewing, or voting on any proposed subdivision in which he has a direct or indirect interest. A member may be disqualified only by Board action in which the member whose qualification is in question shall not vote.

1109	9. <u>Voting</u>
1110 1111 1112	All actions of the Board shall be upon majority vote of the members present at the meeting who are qualified to vote thereon.
1113	10. Appointments
1114 1115	The following persons are appointed to the Board for the term and group indicated:
1116	Name Term Expiring Group or Class
1117	
1118	
1119	
1120	
1121	
1122	
1123	
1124 1125	is hereby appointed as the initial Chairman of the Board.
1126	ARTICLE VII
1127	LEGAL PROVISIONS
1128	1. Criminal and Civil Procedures
1129 1130 1131 1132 1133 1134 1135 1136 1137 1138	From the effective date of this Ordinance, any person who, being the owner or agent of the owner of any land located within the jurisdiction of this Ordinance, either subdivides his land in violation of this Ordinance or transfers or sells land by reference to, exhibition of, or any other use of a plat showing a subdivision of the land before the plat has been approved and recorded pursuant to this Ordinance, shall be guilty of a misdemeanor and shall be subject to a fine and/or imprisonment as provided in North Carolina General Statute 14-4.
1139 1140	The County may enjoin any subdivision, transfer, or sale of land not made in compliance with this Ordinance.

- The description by metes and bounds in the instrument of 1141
- transfer or other document used in the process of selling or 1142
- transferring land shall not exempt the transaction from this 1143
- 1144 Ordinance.

1145 2. Separability

- Should any section or provision of this Ordinance be 1146
- found by a court of competent jurisdiction to be unconstitutional or invalid, such decision shall not affect 1147
- 1148
- the validity of the Ordinance as a whole or any part thereof 1149
- 1150 other than the part so found to be unconstitutional or
- 1151 invalid.

1152 3. Registration of Ordinance

- 1153 In accordance with Article 153A-332 of the General
- 1154 Statutes of North Carolina, the Board of Commissioners shall
- 1155 file a copy of this Ordinance for registration with the
- Register of Deeds for Craven County. 1156

1157 4. Abrogation

- 1158 This Ordinance shall neither repeal, abrogate, annul,
- 1159 impair, not interfere with any existing subdivisions, the
- 1160 plats of which are properly recorded in the Office of the
- 1161
- Register of Deeds prior to the effective date of this Ordinance nor with existing easements, covenants, deed 1162
- 1163 restrictions, agreements, or permits previously adopted or
- 1164 issued pursuant to law prior to the effective date of this
- 1165 Ordinance.

1166 5. Effect on Existing Legislation

- Where this Ordinance conflicts with existing ordinances, 1167
- statutes, or regulations effective in the jurisdiction of 1168
- 1169 this Ordinance and enacted by the County, State, or Federal
- governments or their agencies, then the ordinance, statute, 1170
- 1171 or regulation requiring the higher standard shall apply.

1172	6. Effective Date
1173 1174	This Ordinance shall become effective immediately upon its adoption.
1175 1176	BOARD OF COMMISSIONERS FOR THE COUNTY OF CRAVEN
1177 1178	By:Chairman
1179	APPROVED AS TO FORM:
1180 1181	County Attorney
1182	DATE:

APPENDIX B: APPROVAL OF WATER AND SEWAGE DISPOSAL SYSTEMS

	Public Systems		Community Systems	Individual Systems	SYSTEM
	Any water system owned and operated by Craven County, any municipality, or water district.	Any water system serving greater than nine connections but not owned or operated by any governmental body.	Any water system serving from two to nine connections, inclusively.	Any well, spring, stream or other source used to supply a single connection.	WATER DEFINITIONS
•	Governing body operating said system. Environmental Health Section, Department of Human Resources.	Environmental Health Section, Division of Health Services, N. C. Department of Human Resources.	Craven County Health Department.	Craven County Health Department.	SYSTEMS REGULATORY AGENCY
	Any sewage disposal system owned and operated by Craven County, any municipality or sanitary sewage districts.	or not on septic talks or not connected to a public system.		Any septic tank or privy serving a single source with an effluent discharge of less than 3,000 gal. per day.	SANITARY SEWER SYSTEMS DEFINITIONS REGULA
!	Governing body operating said system. Division of Environmental Management, N. C. Department of Natural and Economic Resources.		Division of Environ- mental Management, NC Department of Natural and Economic Resources.	Craven County Health Department.	ER SYSTEMS REGULATORY AGENCY

APPENDIX C: PRELIMINARY APPLICATION FORM

	Identification: Subdivision Name Subdivider's Name	Nuul C33	
	Location:	Telephone	
	The following information is related expected to be developed in the vici	to the entire tract(s) owned and/or nity by the subdivider:	
•	Tux Nerel ellee(3)		
	Size of tract(s)	Yadiiahaia	
	Residential	Industrial Dublic on Community	
	Other: Spec	ifyFacilities	
	Residential Industrial Public or Community Other: Specify Facilities Describe each (include acreage, typical lot size(s), and the extent to which the subdivider intends to develop).		
•	To be developed in stages? No		
	Area to be developed	acres Number of lots	
•	Expected Method of Maton Supply	Expected Method of Source Collect	
	Public Source Community # Connection Individual	Public Source Community # Cor Individual tic	
•	Expected Method of Street Access		
	Existing Public Street New State Maintained Street(s) New Municipal Street(s): Municipality Private Residential Street(s)		
	Approximate linear feet of new streets to be expected in intiial stage:		



	Flood Plain	
	Slide Area	
	Highly Erodable Soils	
	Poorly Drained Areas	
	Other	
I her	reby certify that the above information	is accurate:
	Signed:	

COMMENTS:

APPENDIX D: PRELIMINARY SITE PLAN CHECKLIST

The following information shall be contained in the preliminary site plan prior to consideration by the Board: NAME OF SUBDIVISION _____ Date Submitted ____ LOCATION SUBDIVIDER _____ ADDRESS _____ TEL. ____ SURVEYOR _____ ADDRESS _____ TEL. ____ ENGINEER _____ ADDRESS _____ TEL. CHECKLIST: A. Base Information: Title Block - Subdivision name, subdivider's name and address, North Arrow, scale (min. 1"=200') denoted graphically and numerically, date of plat preparation, and township, county, and state in which subdivision is located. The boundaries of the tract or portion thereof to be subdivided, distinctl and accurately represented with all bearings and distances shown. Property lines and owner's names of adjoining properties and/or adjoining subdivisions of record. Significant natural features including wooded areas, marshes, major rock outcrops, ponds or lakes, streams, or other natural features affecting the site. Existing physical features including buildings, railroads, easements, bridges, culverts, storm drains, streets, power lines, or utility lines both on the land to be subdivided or immediately adjacent to said land which will either effect or be effected by said subdivision. Topographical contour lines at five foot elevation intervals. Proposed Lot Layout: Proposed lot and street right-of-way lines, building setback lines, easements, lot and block numbers, approximate dimensions, designation of any dedications or reservations to be made, and proposed use of land if other than single family residences. C. Proposed Street Layout:

Sketch view of proposed streets showing pavement widths, curbing if any, street names with location of street sign, and proposed street names.

D.	Propos	sed Sewerage and Water System:	
		Sketch view of proposed water distribution system, if any, and sanit sewerage system if any. Sketch should show approximate line sizes, approximate location of any wells, man holes, fire hydrants, or treatment facilities, and location of connections with existing systems.	·
Ε.	Propos	sed Drainage System:	
		Sketch view of any drainage facilities including any open drainagewa storm sewers, culverts, retaining ponds, or areas where water is to diverted through grading. Sketch should show approximate dimensions of any facilities.	be
F.	Other	Improvements:	
,		Proposed location and description of any other improvements including but not limited to, riding trails, sidewalks or pedestrian ways, reserved open space or recreational facilities, school sites, commercareas, or buffer strips.	•

APPENDIX E: GENERAL DEVELOPMENT PLAN CHECKLIST


The following information shall be included with the general development plan prior to consideration by the Board: NAME OF SUBDIVISION _____ DATE SUBMITTED ____ ADDRESS TEL. LOCATION SUBDIVIDER _____ ADDRESS ____ TEL. ____ SURVEYOR _____ ADDRESS _____TEL. _____ ENGINEER _____ ADDRESS _____ TEL. ____ CHECKLIST: A. Site Plan: A final site plan containing all information required in Appendix D substantially conforming to the approved preliminary site plan where said plan was required. All improvements to be shown with final dimensions. B. Sewer and Water Plans: Final plans and specifications containing all data, calculations, and information required by the appropriate agencies (See Appendix B) and necessary to construct said systems. C. Street Plans: Final plans and specifications for the proposed street system containing all data, calculations, and information required by D.O.T. or the County Engineer and necessary to construct said street. D. Storm Drainage: A final drainage and sedimentation plan containing all data, calculations, and information required by appropriate State of local officials or necessary to describe a drainage system which can meet the objectives set forth in Article 3 Sections 5 and 6 of this Ordinance. E. Environmental Impact Statement: An Environmental Impact Statement, if required, pursuant to Article 5 Section 4.01 of this Ordinance. F. Certificates: (Submitted where required, prior to Board approval - See Article V) 1. Sewer and Water System - signed by appropriate officials. Public Streets - signed by District Engineer of D.O.T.
 Municipal Streets - signed by appropriate municipal official. 4. Erosion and Sedimentation Control - signed by appropriate officials.

APPENDIX F: FINAL PLAT CHECKLIST

CHECKLIST:

ADMINISTRATIVE REQUIREMENTS

		Notice that improvements guar of improvements has been gran	rantee has been accepted or certificatinted;	on	
•		Submitted within twelve (12) unless written extension is	months of general development plan app granted by the Board;	roval,	
Final plat is either 15 by 20 inches or 20 by 30 inches and is a of at least 1" = 200;					
		Five (5) copies submitted; 1	reproducible, 4 copies;		
			Date Final Plat Submitted		
		Date General	Development Plan Approved		
	NAME O	F SUBDIVISION			
	LOCATI	NC			
-	OWNER		ADDRESS	TEL.	
	SURVEY	OR	ADDRESS	TEL.	
		he following information must Plat prior to consideration by	be submitted with, or be contained in, the Board:	the	
		Subdivision name, North Arrowdate of plat preparation, and subdivision is located;	v, scale denoted graphically and numerion township and county and state in which	cally, h the	
			the tract to be subdivided fully dimens the location of intersecting boundary		
		The names and deed references of owners of adjoining properties and adjoining subdivisions of record (proposed and under review);			
		and other such improvements s forming any boundary line of	nts-of-way, watercourses, utilities, roshall be accurately located where cross the property shown, and locating offse ted in broken lines with azimuths or co	ing or t or	



Certificate of Survey and Accuracy signed by the Surveyor:

Date *Certificate of Completion and Warranty signed by the Subdivider;

Date

*Certificate of Dedication and Maintenance signed by the Subdivider;

Date

*Certificate of Improvements signed by the Director of Public Safety;

Date

Certificate of Approval of the Final Plat signed by Chairman of the Board.

Date

(*To appear on Final Plat if improvements are completed prior to

final plat review or as separate document if guarantees are used.)

See 3B Supp. of N.C.G.S.

APPENDIX G: ADMINISTRATIVE FORMS

- 1. Certificate of Improvements
- 2. Certificate of Completion and Warranty
- 3. Certificate of Dedication and Maintenance
- 4. Improvements Guarantee Agreement
- 5. Performance Bond
- 6. Irrevocable Letter of Credit
- Certificate of Approval of Water Supply and Sewage Disposal System(s)
- 8. Certificate of Survey and Accuracy
- Certificate of Approval by Division of Highways (public streets)

1.	CERTIFICATE	OF IMPROVEMENTS

The following improvement	s have been completed by
	name of subdivider
in	Subdivision.
List Completed Improvements:	
to the standards set fort constructed as prescribed	en inspected by my office, have been built according h in the Craven County Subdivision Ordinance and are by the approved General Development Plan. To my ts (contain no defects) (contain only the following be approved.
List any known defects:	
Date	Director of Public Safety for the
	County of Craven

2. CERTIFICATE OF COMPLETION AND WARRANTY

The undersigned certifies that he is an officer, to-wit: the (title of Officer) of (name of corporation), a corporation, and that he has been authorized to execute this Certificate pursuant to authority granted by resolution of the Board of Directors of (name of corporation), copy of which resolution is attached hereto.

(name of corporation), through the undersigned, hereby certifies that the following improvements required under the authority of the Craven County Subdivision Ordinance have been installed as specified by the approved General Development Plan for Subdivision and that said improvements are in compliance with the minimum standards specified by said Ordinance and by the Craven County Subdivision Review Board for the construction of said improvements:

List Completed Improvements:

<u>(name of corporation)</u>, through the undersigned, further certifies that it knows of no defects from any cause and will fully warrant said improvements to be free from defects in material and workmanship for a period of one year from this date. In the event defects are discovered in any of said improvements during said period, (name of corporation) will replace and/or repair the defective improvements at its own expense. (name of corporation) Secretary by: Date: STATE OF NORTH CAROLINA COUNTY OF CRAVEN 1, ______, Notary Public of said State and County certify that _____ _____personally came before instrument was signed in its name by its President, sealed with its corporate seal, and attested by self as its ____ Secretary. Witness my hand and notarial seal, this the _____ day of _____, Notary Public My Commission Expires:

(This certificate may be appropriately modified for execution by a subdivider who is not incorporated.)

	Certificate of Dedication and Maintenance
	The undersigned certifies that he is an officer, to-wit: the (title of Officer) of (name of corporation), a corporation, and that he has been authorized to execute this Certificate pursuant to authorit granted by resolution of the Board of Directors of (name of corporation), copy of which resolution is attached hereto.
	<pre>(name of corporation) , through the undersigned hereby certifies that all property and improvements described on the final plat for</pre>
Lis	t any encumbrance or lien:
	(name of corporation) , through the undersigned, freely dedicates all required rights-of-way, easements, streets, utilities, open space, and other improvements to public or private use as noted on said Final Plat and freely establishes minimum building setback lines as required by the Craven County Subdivision Ordinance. (name of corporation) further (assumes full responsibility for) (has made arrangements suitable to the Craven County Subdivision Review Board for) the maintenance of said improvements which (assumption of responsibility) (arrangements) shall remain in effect until such time as said improvements are accepted for maintenance by an appropriate public body.
	(name of corporation
	Ву
Att.	Byest:
Att	Byest:Secretary
Att	est:Secretary
Dat STA	est:Secretary
Dat STA COU I, Cou bef Sec and	est: Secretary e: TE OF NORTH CAROLINA NTY OF CRAVEN Notary Public of said State and personally came ore me this day and acknowledged that (s)he is retary of that by authority duly given and as the act of the corporation,
Dat STA COU I, Cou bef Sec and the Pre	est: Secretary e: TE OF NORTH CAROLINA NTY OF CRAVEN Notary Public of said State and personally came ore me this day and acknowledged that (s)he is
Dat STA COU I, Cou bef Sec and the Pre as	est: Secretary e: TE OF NORTH CAROLINA NTY OF CRAVEN Notary Public of said State and personally came ore me this day and acknowledged that (s)he is retary of that by authority duly given and as the act of the corporation, foregoing instrument was signed in its name by its sident, sealed with its corporate seal, and attested by self
Dat STA COU I, Cou bef Sec and the Pre as	e: TE OF NORTH CAROLINA NTY OF CRAVEN Notary Public of said State and personally came ore me this day and acknowledged that (s)he is retary of, a corporation, that by authority duly given and as the act of the corporation, foregoing instrument was signed in its name by its sident, sealed with its corporate seal, and attested byself its Secretary. ness my hand and notarial seal, this the day of,

(This certificate may be appropriately modified for execution by a $\operatorname{subdivider}$ who is not incorporated.)

4. Improvements Guarantee Agreement

STATE OF NORTH CAROLINA

AGREEMENT

COUNTY OF CRAVEN
THIS AGREEMENT MADE AND ENTERED INTO this the day of,
19 by and between(Subdivider),
hereinafter known as "the Subdivider", and the Craven County Subdivision Review
Board, hereinafter known as "the Board", which Board is also a duly constituted
agency of the County of Craven.
WITNESSETH:
WHEREAS, the Subdivider is attempting to secure from the Board approval
of a Final Plat of a proposed subdivision to be known as the
Subdivision to be located in Craven County, North Carolina; and
WHEREAS, a County ordinance entitled Subdivision Ordinance for the County
of Craven, as adopted by the Board of Commissioners for the County of Craven
on the day of, 19, (and as subsequently amended),
requires the completion of certain improvements prior to Final Plat approval
by the Board; and
WHEREAS, said Ordinance also allows the Board, at its discretion, to permit
the Subdivider to (post a surety bond) (deposit cash or other instrument readily
convertible into cash at face value) with the County of Craven through the
Board to guarantee the completion of said required improvements; and
WHEREAS, the Board desires to approve said Final Plat and, in lieu of
requiring completion of all improvements prior to said approval, will accept
from the Subdivider the filing of a (surety performance bond with
Company as surety) (letter of credit from the
Bank) (other) to guarantee and secure completion of
said improvements.
IT IS THEREFORE, AGREED AS FOLLOWS:
1. The Subdivider will, on or before the day of,
19, complete as required the following improvements in the
Subdivision:
(here detail all improvements to be completed)

The Subdivider shalla (enter here the type			-
ing completion of sai		·	-
 When the (enter here other requirements of Final Plat of the 	f said Ordinance are	met, then the Bo	
The Craven County Sub	odivision Review Boa	rd has, by approp	oriate Board action,
caused this Agreement to	be executed by its	Chairman or other	authorized member
and attested by the Clerk	c to the Board, and	the <u>(name</u>	of company)
has, by appropriate actio			-
be executed by its		and attested by	its
Secretary under corporate	e seal, this the	day of)
19			
	Cmayon (County Subdivision	Doview Roamd
	Craven o	ouncy Subarvistor	i Keview Doard
	Ву		
		Chairma	n
Attest:		·	,
Clerk to the Board			
		Inama of compan	nation)
•	Secretaria de Carta d	(name of corpor	acton)
•	Ву		
•	J	Presider	nt
Attest:			
Secretary	_		
seci e cary			

STATE OF NORTH CAROLINA

COUNTY OF CRAVEN

Ι,	_, Notary Public for said State and County
certify that	personally came before me this day and
acknowledged that (s)he is	Secretary of
	uly given and as the act of the corporation,
the foregoing instrument was signed	in its name by its
President, sealed with its corporat	e seal, and attested byself as its
Secretary.	
Witness my hand and notarial se	al, this theday of,
19	,
	Notary Public
·	Notary Public
My Commission Expires:	
(This Agreement may be appropriately who is not incorporated.)	y modified for execution by a Subdivider -

5, Performance Bond

STATE OF NORTH CAROLINA COUNTY OF CRAVEN

PERFORMANCE BOND

KNOW ALL MEN BY THESE PRESENTS that we,
(name of Subdivider), as Principal, and
(the name of the Bonding Company) as surety, are held and firmly
bound unto the County of Craven, a political subdivision of the State of
North Carolina, and a body politic and corporate, in the sum of \$,
lawful money of the United States of America, for the payment of which, well
and truly to be made, we, and each of us, bond ourselves and each of us, our
successors and assigns, jointly and severally, by these presents.
THE CONDITIONS OF THIS OBLIGATION ARE SUCH THAT:
WHEREAS, the Principal has submitted a Final Plat of the subdivision
known as Subdivision, located in Craven
County, North Carolina, for approval by the Craven County Subdivision Review
Board, an agency of the County of Craven, which approval is a condition preceden
to the right of said Principal to have said final plat registered in the Office
of the Register of Deeds for Craven County; and
WHEREAS, the Craven County Subdivision Review Board is unable, pursuant
to County ordinance, to approve said plat of said Subdivision for registration
until all required improvements are completed or until a guarantee of comple-
tion of said required improvements is filed with the County of Craven through
said Subdivision Review Board; and
WHEREAS, the Craven County Subdivision Review Board and the Principal
have this date entered into an Agreement by which said Board will approve
Principal's final plat for the Subdivision

prior to the completion of requ	ired improvemen	ts, and the Pri	ncipal has	agreed
to file a Surety Bond in the am	ount of \$	secur	ing to the	County
of Craven, through said Board,	the actual comp	letion of said	required i	mprove-
ments on or before the	day of	, 1	9, wh	ich Agree
ment is attached hereto as Exhi	bit A and made	a part hereof;	and	
WHEREAS, the improvements r	equired and agr	eed to be comple	eted are s	et forth
in said Exhibit A.				
NOW THEREFORE, if the Princ	ipal shall full	y comply with a	ll the ter	ms
hereof, including the requireme	nts of that Agr	eement attached	hereto as	Exhibit
A and by which the Principal ag	rees to complet	e certain impro	vements on	or
before theday of		19, then t	his obliga	tion shal
be null and void; otherwise, it	shall remain i	n full force and	d effect.	
IN WITNESS WHEREOF the said	Principal and	Surety have her	eunto set	their
hands and seals this the	day of		, 19	•
·	***************************************	Principal		
	Ву	President	:	(SEAL)
		President		
Attest:			•	
	annadi na taganagan yang didan saran sanadi		. ·	
		Surety		
		ou. coj		(
		Attorney-in-Fac		(SEAL)
	(Power	of Attorney at	tached)	

6. <u>Irrevocable Letter of Credit</u>

STATE OF NORTH CAROLINA COUNTY OF CRAVEN	IRREVOCABLE LETTER OF CREDIT
	NO.
(Nam	e of Bank)
Address: (incl	uding branch, if any)
	Date:
TO: THE COUNTY OF CRAVEN c/o BOARD OF COMMISSIONERS F THE COUNTY OF CRAVEN CRAVEN COUNTY COURTHOUSE NEW BERN, NORTH CAROLINA 28	
Commissioners:	
We hereby open our irrevocab	le credit in your favor available by your
drafts at sight on us for a sum n	ot exceeding \$ for the account
of	hereinafter know as "Customer". When presented
for negotiation, drafts must be a	accompanied by the signed statement of the
Chairman of the Craven County Sub	odivision Review Board that drawing is due
to default or failure to perform	by Customer, the following improvements in
the	Subdivision on or before the day of
	:
(Here list the	required improvements)
The term of this irrevocable	e credit is either through and including the
day of	, 19, or upon written notice from the
Chairman of the Craven County Sub	odivision Review Board that the required
improvements have been timely com	mpleted, whichever is earlier.
Acting through the Chairman	of the Craven County Subdivision Review
Board, you will notify us when e	ither of the following occurs:

- The required improvements have been timely completed and the credit may be released; or
- 2. The Customer has failed to perform or is in default thereunder.

All drafts drawn hereunder must be marked as follows:

The amount of any draft drawn under this credit must, concurrently with negotiation, be endorsed on the reverse side hereof, and the presentment of any such draft shall be a warranty by the negotiating band that such endorsement has been made.

This Letter of Credit shall be transferrable and/or assignable.

This Letter of Credit, except as otherwise expressly provided herein, is governed by the Uniform Commercial Code in force in the State of North Carolina on the date hereof.

Very truly yours,	
(Name of Bank)	
By:(Authorized Signature)	

Certificate of Approval of Water St	upply and Sewage Disposal System
I hereby certify that the water sup	oply and sewage disposal systems
(installed) (proposed for installation)	and specified on the General
Development Plan for	Subdivision
meet all pertinent State and local requ	rirements and are hereby approved.
	<u> </u>
-(1 -(1	o be signed by the appropriate State or local official(s) - See Appendix B)
	(Agency)
DATE	
DATE:	



8. Certificate of Survey and Accuracy

(For purposes of this Ordinance, the following shall constitute substantial compliance with North Carolina General Statute 47-30, as amended.)

•	I hereby certify that this map was (drawn by me) (drawn under my super-
	vision) from (an actual survey made by me) (an actual survey made under my
	supervision) (a deed description recorded in the Office of the Register of
	Deeds for Craven County in Deed Book at page, Deed Book
	at page, etc.) (other); that the error of closure as calculated by
	latitudes and departures is 1:; that the boundaries not surveyed are
	shown as broken lines plotted from information found in deed descriptions
	recorded in said Register's Office in Deed Book at page; that
	this map was prepared in accordance with N. C. G.S. 47-30, as amended.
;	Witness my hand and seal this the day of,
	19
	Registered Surveyor or Professional Engineer
	License or Registration Number

9. <u>Certificate of Approval by Division of Highways</u> (Public Streets)

The form for this Certificate is provided by a District Engineer of the Division of Highways of the North Carolina Department of Transportation.

